## MYSORE DIVISION.

*Notice dated 25th September* 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 20th October 1928, for restoring Hiduva Tank Registered No. 24 of Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Each tender must be accompanied by a deposit of Rupees one thousand only (Rs. 1,000) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Hiduva Tank Register No. 24 of Nagamangla Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be noted for eash items of work.

10. The quotations must be clearly specified and no vague items such as as per rate and 15 per cent or etc., can be accepted.

11. No claim for higher rate than those accepted can be entertained after the works started or after the completion.

Abstract estimate for restoring Hiduva Tank, Registered No. 24 of Nagamangla Taluk.

| Sl. No. | Items of work | Per | Rate | Quantity | Cost | Total |
|---|---|---|---|---|---|---|
| | I. BUND. | | | | | |
| 1 | Clearing jungle L S. rupees ... | C. yds. | | ... | | |
| 2 | Cutting grips in old bund ... ... | ,, | | 26½ | | |
| 3 | Earthwork excavation for seat of bund. | ,, | | 294 | | |
| 4 | Excavating soft rock ... | ,, | | 607 | | |
| 5 | Earth work excavation for foundation of revetment and using to bund. | ,, | | 520 | | |
| 6 | Burnt or split stone in surki mortar ... | C.ft. | | 1501 | | |
| 7 | Puddle wall with good gravel and clay. | C. yds. | | 268 | | |
| 8 | Earth work to bund including watering and tamping with lead and extra ramps. | ,, | | 42040 | | |
| 9 | Gravel backing to revetment including carting and consolidating. | ,, | | 1681 | | |
| 10 | New stone work including carting, etc. | ,, | | 3164 | | |
| 11 | Resetting old stone work with new jelly. | L. S. Rs. | | ... | | |
| 12 | Turfing ... ... | Sqr. | | 1803·50 | | |
| 13 | Preparing and fixing grade stones and bed stones with cutting figures and painting, etc. | Each | | 30 | | |
| 14 | Visanis stones ... ... | ,, | | 30 | | |
| 15 | Bench mark stones ... ... | ,, | | 2 | | |
| 16 | Register No. stone ... ... | ,, | | 1 | | |
| 17 | Date stone ... ... | ,, | | 1 | | |
| 18 | Gauge stone ... ... | ,, | | 2 | | |

| Sl. No. | Items of work | Per | Rate | Quantity | Cost | Total |
|---|---|---|---|---|---|---|
| | II. BREACH FILLING. | | | | | |
| 1 | Excavation soft rock ... ... | C.yds. | | 5,720 | | |
| 2 | Baling out water including ring bund | L. S. Rs. | | | | |
| 3 | Earthwork excavation for slipping ... | C.yds. | | 151 | | |
| 4 | Wedging and removing hard rock ... | " | | 38 | | |
| 5 | Excavation soft rock .. ... | " | | 50 | | |
| 6 | Burnt or split stone in surki mortar ... | " | | 2677 | | |
| 7 | Puddle wall with gravel and clay ... | C.ft. | | 1516 | | |
| 8 | Earthwork to breach including watering and tamping with 400 feet lead and 15 ft. lift and mixture of soils. | C.yds. | | 22227 | | |
| 9 | Gravel backing including carting and consolidating. | " | | 534 | | |
| 10 | New stonework ... ... | " | | 1391 | | |
| 11 | Turfing ... ... ... | Sqr. | | 179·47 | | |
| 12 | Protective works during closure of breach in 2 seasons if necessary during construction. | L. S. Rs. | | | | |
| | LEFT WASTE WEIR. | | | | | |
| 1 | Excavation in hard gravel and soft rock | C.yds. | | 500 | | |
| 2 | Concrete in surki mortar .. ... | C.ft. | | 3043 | | |
| 3 | Burnt or split stone in surki mortar ... | " | | 16873 | | |
| 4 | Burnt stone slab 6" thick dressed and fixed in surki mortar | S.ft. | | 1012 | | |
| 5 | Cement pointing ... ... | Sqr. | | 9·85 | | |
| 6 | Surki mortar pointing ... ... | " | | 80·00 | | |
| 7 | New stone work ... ... | C.yds. | | 4500 | | |
| 8 | Resetting old stone with new jelly ... | " | | 212 | | |
| | RIGHT WASTE WEIR. | | | | | |
| 1 | Excavation soft rock ... ... | " | | 330 | | |
| 2 | Concrete in surki mortar ... ... | C.ft. | | 1345 | | |
| 3 | Burnt or split stone in surki mortar .. | " | | 5166 | | |
| 4 | Burnt stone slab 6" thick dressed and fixed in surki mortar. | S.ft. | | 442 | | |
| 5 | Cement pointing ... ... | Sqr. | | 4·18 | | |
| 6 | Surki pointing ... ... | " | | 26·55 | | |
| 7 | New stone work ... ... | C.yds. | | 550 | | |
| 8 | Resetting old stones with new jelly ... | " | | 30 | | |
| 9 | Cushion wall as may be necessary during construction. | L. S. Rs. | | | | |
| | CONSTRUCTING A NEW SLUICE. | | | | | |
| 1 | Earthwork cutting bund ... ... | C.yds. | | 269 | | |
| 2 | Dismantling and removing revetment ... | " | | 29 | | |
| 3 | Earthwork excavation in harder soil ... | " | | 61 | | |
| 4 | Concrete in surki mortar .. ... | C.ft. | | 1719 | | |
| 5 | Burnt stone in surki mortar ... | " | | 2487 | | |
| 6 | Burnt stone slabs dressed and fixed 6" thick. | Sft. | | 774 | | |
| 7 | Surki pointing ... ... | Sqr. | | 12·81 | | |
| 8 | Cement pointing ... ... | " | | 5 77 | | |
| 9 | Providing teakwood plug and rod with locking arrangement | L. S. Rs | | | | |
| 10 | Filling with earth with consolidation ... | C.yds. | | 156 | | |
| 11 | Old stone work available at site ... | " | | 12 | | |
| 12 | Gravel backing ... ... | " | | 18 | | |
| 13 | Turfing ... ... ... | Sqr. | | 20·56 | | |

| Sl. No. | Items of work | Per | Rate | Quantity | Cost | Total |
|---|---|---|---|---|---|---|
| | **ACQUEDUCT No 1.** | | | | | |
| 1 | Excavation soft rock ... ... | C.yds. | | 236 | | |
| 2 | Concrete in surki mortar ... ... | C.ft. | | 1138 | | |
| 3 | Burnt or split stone in surki mortar ... | ,, | | 3040 | | |
| 4 | Burnt brick in surki mortar ... | ,, | | 2049 | | |
| 5 | Burnt stone pillars including, dressing and fixing. | ,, | | 345 | | |
| 6 | Burnt stone slab including dressing, fixing and pointing. | S.ft. | | 2373 | | |
| 7 | Surki mortar plastering ... .. | Sqr. | | 13·55 | | |
| 8 | Pointing with surki mortar ... | ,, | | 19·69 | | |
| 9 | Cement plastering ½" thick ... | ,, | | 5·48 | | |
| 10 | Earthwork to bund including watering and tamping. | C.yds. | | 1568 | | |
| 11 | New stone work ... ... | ,, | | 248 | | |
| 12 | Clearing approaches ... ... | L. S. Rs. | | | | |
| | **FOOT BRIDGE No. 2.** | | | | | |
| 1 | Earthwork excavation ... ... | C.yds. | 2 | 1 | | |
| 2 | Concrete in surki mortar ... ... | C.ft. | 2 | 18 | | |
| 3 | Burnt brick in surki mortar ... | ,, | 2 | 35 | | |
| 4 | Burnt stone slab 6" thick dressed and fixed. | S.ft. | 2 | 12 | | |
| 5 | Surki mortar plastering ... ... | Sqr. | 2 | .66 | | |
| 6 | Clearing site ... ... | L. S. Rs. | | | | |
| | **CART BRIDGE No. 1.** | | | | | |
| 1 | Earthwork excavation ... ... | C.yds. | | 6 | | |
| 2 | Burnt brick in surki mortar ... | C.ft. | | 386 | | |
| 3 | Burnt stone slab 6" thick ... ... | S.ft. | | 160 | | |
| 4 | Surki mortar plastering ... ... | Sqr. | | 2·62 | | |
| 5 | Filling in road approaches ... | L. S. Rs. | | | | |
| 6 | Clearing site ... ... | ,, | | | | |
| | **RELIEVING WEIR 50′ × 25′** | | | | | |
| 1 | Earthwork excavation ... ... | C.yds. | 1½ | 33 | | |
| 2 | Removing sides up to bed of Hulla ... | L. S. Rs. | | | | |
| 3 | Concrete in surki mortar ... ... | C.ft. | 1½ | 568 | | |
| 4 | Burnt brick in surki mortar ... | ,, | 1½ | 523 | | |
| 5 | Burnt stone slab 6" dressed and fixed ... | S.ft. | 1½ | 175 | | |
| 6 | Broken jelly new including lead ... | C.yds. | 1½ | 37 | | |
| 7 | New stone work ... ... | ,, | 1½ | 74 | | |
| 8 | Surki mortar plastering ... ... | Sqr. | 1½ | 4·14 | | |
| 9 | Filling approach ... ... | L. S. Rs. | | | | |
| 10 | Clearing site ... ... | ,, | | | | |
| | **IRRIGATION SLUICE 6" DIA PIPE.** | | | | | |
| 1 | Earthwork excavation ... ... | C.yds. | | 2 | | |
| 2 | Burnt brick in surki mortar ... | C.ft. | | 55 | | |
| 3 | Surki mortar plastering ... ... | Sqr. | | ·78 | | |
| 4 | Cast iron pipe 6′ Dia 9′ long including Railway freight and carting charges, etc. | Cwt. | | 2½ | | |
| 5 | Clearing site ... ... | L. S. Rs. | | | | |

| Sl. No. | Items of work | Per | Rate | Quantity | Cost | Total |
|---|---|---|---|---|---|---|
| | LEFT SLUICE CHANNEL. | | | | | |
| | Excavation gravelly soil ... | C.yds. | | 5062 | | |
| 2 | Do soft rock ... | ,, | | 1724 | | |
| 3 | Cutting blasting rock ... | L. S. Rs. | | ... | | |
| 4 | Preparing and fixing mile stone | Each | | 4 | | |
| 5 | Do furlong stone ... | ,, | | 45 | | |
| 6 | Do bed grade stone ... | ,, | | 49 | | |
| 7 | Natural weir ... | No. | L. S. Rs. | 4 | | |
| 8 | Irrigation sluice ... | ,, | ,, | 27 | | |
| 9 | Improving cart track ... | L. S. Rs. | | | | |
| 10 | Wells and sanitation ... | ,, | | | | |
| 11 | Sheds for inspection staff ... | ,, | | | | |

N. G. KRISHNAINGAR,
*Executive Engineer.*

## MYSORE POWER AND LIGHTING, ELECTRICAL DEPARTMENT.

*Notification of tenders dated 30th September 1928.*

Notice is hereby given that sealed tenders will be received in the Office of the Superintendent, Power and Lighting, Mysore, by 2 P.M., on the 25th October 1928, for (1) constructing Switch room, Office and Stores (2) constructing one blocks of two Operators Quarters and constructing two units of latrine at Nanjangud. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The works should be completed within four months.

2. The plans, detailed estimates and conditions may be seen at the Office of the Superintendent, Power and Lighting, Mysore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be accompanied by a statement in the form annexed showing the rates in words and figures at which the different items will be executed.

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Tenders will be opened on the 27th October 1928 at 2 P.M.

5. Percentages less than or above estimates rates will not be accepted.

6. Each tender must be accompanied by a deposit of Rs. 500, Rs. 150 and Rs. 50 respectively in cash or Government Promissory Notes, as earnest money, and be superscribed as "Tender for constructing Switch room, Office and Stores" Tender for constructing one block of Two Operators Quarters and "Tender for constructing two units of latrine at Nanjangud" separately.

7. The final acceptance of the tender, will rest with the Superintendent who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

8. Within eight days of the acceptance of the tender, the successful tenderer will be equired to execute the usual contract bonds, in default of which his tender will be considered s cancelled and his earnest money forfeited.